Solar at Sea II

Nationaal Consortium Zon op Water

Bastiaan van den Berg 11 January 2023

- Introduction
- Solar@Sea II
 - Concept
 - Demo Oostvoorne
 - Tests
 - Lessons learned
- Next phase
- Q&A



Solar@Sea II Consortium





bluewater








Solar@Sea Project Overview

bluewater



Solar@Sea Concept - Vision

Design from start with commercial application in mind

- Materials
- Fabrication
- Transport
- Installation
- Operation

Solar@Sea Concept - Floater


bluewater

Double walled fabric drop stitch floaters

Thin film P/V panels on top

Flexible system, moving with the waves








bluewater


Solar@Sea Concept - Floater



Solar@Sea Concept – Solar panels

Flexible PV modules (CIGS tested)


- Light weight
- No significant degradations under frequent small deformations
- Commercially available in lengths up to 6 m
- Certified for salt spray
- Efficiency increasing every year
- Costs will drop significantly by 'economy of scale'. Production techniques maturing.









Solar@Sea Concept - Mooring system




Solar@Sea Concept - Installation



Demo Oostvoorne




- Full scale Oostvoornse Meer
- November 2021 November 2022




Demo Oostvoorne



Tests - Structural properties floater



three point bending test of the dropstitch floater



Tests - Mechanical degradation



Test module (50x40 cm²) with flexible CIGS cells in vertical orientation.

Experiment

Wave	Period	Length	Wave	Maximum	Maximum
type	(s)	(m)	height (m)	bending	theoretical
				height (mm)	strain (%)
1	4.5	31	0.8	0.96	1.24
2	5.2	43	0.9	0.61	0.79
3	5.4	44	1.2	0.76	0.98
4	5.3	44	2.4	1.55	2.00

Dominant wave types at the North Sea (columns 1-4), and the resulting bending and strain on a 50x40 cm² test module (columns 5 &6)

Dancing Beetle

bluewater


Tests – Basin, uplift












bluewater

Tests - Basin, full scale









- Performed at Marin, May 2021
- Wave and drag tests
- Full scale floater


➤ Limits on wave height



Tests – Basin, full scale



Tests - Fouling




bluewater

Tests - Fouling

Coated and uncoated PV panel

March



July

LS



Uncoated


Tests - Manufacturability

- Analysed peel strength of different joining methods for double wall fabrics (DWFs)
- Explored concepts for mass production of floaters









Analysed the effects of material aging on tensile strength and tear resistance of

DWFs







Demo Oostvoorne - Lesson learned

- Pressure impressively well kept
- Structural behaviour non-linear
- Floater moves well with waves
- Fouling only on perimeter
- During dry summer period built-up of bird deposits
- Adhesion of panels to floater not in line with results from lab conditions

New technologies - High potential

- Material Limited use
- Fabrication Onshore, mass production
- Transport Limited logistics, low volumes
- Installation Normal workboats. Mooring can be pre-laid.
- Operation Easy accessible

Next phase

Jan 2023: Project kick-off Solar@SealII

- Offshore environment
- Electrical export cable
- Modelling & testing



Solar@Sea Concept - Maintenance

